



## NOTES

1. FLOW COMPUTER SHALL BE LOCATED NEXT TO THE ASC PANEL.
2. FLOW METER SHALL BE INSTALLED BY CONTRACTOR. AFTER INSTALLATION, THE OWNER SHALL PERFORM ANY NECESSARY CALIBRATIONS. AFTER CALIBRATION, THE CONTRACTOR SHALL INSULATE THE ENTIRE ASSEMBLY.
3. FLOW METER SHALL BE INSTALLED IN ACCORDANCE TO MFG. INSTALLATION PROCEDURE.

# B CHILLED WATER MAGNETIC FLOW METER DETAIL

NO SCALE